



Ref: AMP/FM/TUK/DSO/22
February 17, 2022

TENDER NOTICE

CIVIL WORKS – RENOVATION WORK OF PIA SALES OFFICE BUILDING TURBAT

Seal un-conditional tenders are invited from PIA 'B' class approved enlisted Civil contractors for the subject work. Tender should be addressed to General Manager (Facilities Management) and dropped in Finance Manager Works office (2nd floor PIA Head Office Building Karachi) by March 7th , 2022 till 15:00 hrs and will be open on the same day at 15:30 hrs in the office of General Manager Facilities Management. All details regarding the tender can be downloaded from www.piac.com.pk.

2 % Earnest money of the bid should be attached with the tender.

On the face of envelop reference must be written AMP/FM/TUK/DSO/22

GENERAL MANAGER
(FACILITIES MANAGEMENT DIVISION)
1ST FLOOR, FLIGHT OPERATION BUILDING
PIA HEAD OFFICE.
Tel: 021-9904640
Email: gm.facilitiesmanagement@piac.aero

COPY TO:

1. FINANCE MANGER(W&P)
2. NOTICE BOARD



TENDER FORM

M/s _____

Ref: AMP/FM/TUK/DSO/22
February 17, 2022

DESCRIPTION OF WORK: -

CIVIL WORKS – RENOVATION WORK OF PIA SALES OFFICE BUILDING TURBAT

Dear Sir,

Please send not later than **March 7th, 2022** you're sealed quotations for the items mentioned in the attached sheet as per following terms and condition.

1. PIA reserves the right to accept or reject any quotations without assigning any reason as per PPRA rules.
2. An earnest-money of **2%** in the shape of pay-order/Bank Draft in favor of PIA is to be attached with quotation as earnest money.
3. Tender will be opened by on **March 7th, 2022** at **15:30** Hours by the under signed in presence of the contractors who care to attend.
4. Your quotation should remain valid up to **Three Months**.
5. Period required for completion of project is **Two months**.
6. All works/sample/design will be executed / approved by the engineer on duty.
7. PIA reserves the right to cancel the work order at any stage of the work without assigning any reason as per PPRA RULE # 33.
8. PIA accepts only standard materials of original manufacturer strictly in accordance with the specifications. Any inferior or sub-standard materials, if used, shall be rejected out-rightly and registration of the contractor concerned may be cancelled.
9. PIA shall have the option to increase or decrease the quantity of any item mentioned in the quotation / work order.
10. The firm to whom the contract is awarded shall have to abide by the rules and regulations mentioned in the work order and as well as the all rules & regulations of PIA, PEC and PPRA.

For: **Pakistan International Airlines**

Seal & Signature
Of the contractor



11. No excuse of non – availability of materials of fluctuation in the market rates etc. shall be accepted after the work order is issued.
12. Security deposit 10% will be deducted from each running bill and same will be returned after six months. In case of any discrepancy found, the same will be withheld without prior notification.
13. If the work is delayed after given time period, Rs. 2000 / day will be deducted, up to max. 10% of total project cost.
14. The attached Performa of permit to work is mandatory job to be followed at the time of award of work. Annexure 'A'

Seal & Signature
Of the contractor

For: **Pakistan International Airlines**



M/s _____

 Ref: AMP/FM/TUK/DSO/22
 February 17, 2022

BOQ Civil Work					
SR. No.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
1	DISMANTLING Carefully taking up or down, glazed or encaustic tiling to floors, hearths or walls incl borders, skirting, moldings, capping etc and CM setting, but not backing.	1,303	Sft		
2	Burnt brick work Burnt brick work, in walls 115 mm thick, laid and jointed in CM 1:3, straight or to curve with inner radius of 6m and over, upto G.F roof level.	1640	Cft		
3	Cleaning of Soak Pit Complete cleaning of soak pit and removal of all types of Debris away from PIA premises as desired by in charged Engineer.	2	L.S		
4	Plaster Work Hacking out Cement Plaster of walls or lathing, racking out joints when required, or racking out cement jointing to walls, roofs or floors of any description hacking out concrete to form key, or dismantling, lathing with or without plaster.	1,200	Sft		
5	Plaster Work Providing and laying ordinary plaster of 1/2" thick with cement mortar 1:4 using approved quality specified river sand in any floor on external works including all corners, recessed areas, window/door edges, hacking the concrete surfaces scaffolding and curing complete in all respect as per drawings / specifications and as per directions of the Consultants / Engineer-In-Charge. All plaster to finish smooth flat in true level, line and plumb and properly mixed. Galvanized Iron mesh (8" wide) at joints between masonry and RCC Columns/ Beams/ slab.	3,200	Sft		

 For: **Pakistan International Airlines**

 Seal & Signature
 Of the contractor



6	Bathroom Tiles Providing and laying, Bathroom tiles glazed / unglazed in any colour / print / texture exc 12" x 24" inches each on walls and floor, set in neat cement with bond and joints grouted with white / coloured cement, complete all as specified, as desired by incharged Engineer.	1,303	Sft		
7	Aluminum door closer Supply and fix, Aluminum door closer (Deluxe model) anodized bronze.	8	Each		
8	Wooden Door Supply and fix, Hollow Flush Door, Commercial Veneered, 32mm thick including mongery, all as specified, without chowkats, complete in all respects, as desired engineer in charge	126	Sft		
9	Glazing Supply and fix, Plain Sheet glass 5mm thick, fixed to timber or steel sashes with putty as specified.	200	Sft		
10	P/F Imported quality Roller Blind of approved quality as per desired engineer incharge.	350	Sft		
11	Gypsum Ceiling Supply and fix, Gypsum Ceiling 600mm x 600mm x 7.5mm thick, incl Aluminum Tee & Aluminum angle, 25mm x 25mm x 1mm, incl hanger clips, jointing clips and 14 SWG, GL wire etc, complete.	876	Sft		
12	Interior Paint Providing and applying 2 coats of plastic emulsion/matt finish paint on interior walls after removing / scraping the white / colour wash and distemper from plastered / un-plastered surface, complete in all respects.	9900	Sft		
13	Roof Paint Distemping Providing and applying 2 coats of with Poly Vinyl Distemper or equivalent, on new or old surface	1200	Sft		
14	Exterior Paint Providing and applying 2 coats of Weather Resistant paint on exterior walls after removing / scraping the white / colour wash and distemper from plastered / un-plastered surface, complete in all respects.	7000	Sft		

 For: **Pakistan International Airlines**

 Seal & Signature
 Of the contractor



15	Roof Treatment Supply and fix, Asphalt-based Jute Felt 70 lbs., bituminous, in flashing and concrete / brick work joint, joint wedged and tucked inside end joints, stuck with 2 coats of bitumen 10/20 applied hot @ 4.90 kg/10sqm with 3mm Coarse aggregate, complete in all respect, as desired by incharged Engineer.	4600	Sft		
16	PLUMBING WORK				
17	Supply and Fix Wash Hand Basin (WHB) of standard quality, including pedestal, wastepipe, bolts/bracket and coupling etc., complete all as specified.	2	Each		
18	Providing and laying of Special colour Vanity Bowl glazed ware one hole complete with bottle trap, waste coupling ,chain and plug best quality Mixture approved by Engineer	2	Each		
19	Supply and fix, WC Asiatic pattern (white colour incl foot rest, full Orrisa pattern or equivalent) 13 lit flushing cistern, low down (plastic), flush pipe etc fixed to concrete, brick, stone or wood work, Supply and fix, WC Asiatic pattern (white colour incl foot rest, full Orissa pattern or equivalent) 13 lit flushing cistern, low down (plastic), flush pipe etc fixed to concrete, brick, stone or wood work, high quality as approved by Engineer	2	Each		
20	S/F of Urinal Apparatus basin /stok Porta design or equivalent best quality pattern complete incl all kind of connection Brass, stop/tee cock as directed by Engineer	1	Each		
21	Supply and fix, Mirror, (any shape and pattern), 5mm thick, edges ground, complete all as specified.	15	Sft		
22	Toilet Paper holder high quality as approved by Engineer	2	Each		
23	Fancy Double Bib Cock Brass, high quality as approved by Engineer	2	Each		
24	Supply and Fix, Toilet shower, 15 mm dia.	2	Each		
25	CP Mixer 15mm dia fancy head including tee kock and tee connections, high quality as approved by Engineer	2	Each		
26	Supply and fix, Soap/sponge tray any shape, pattern and size with plugs, screws etc. complete all as specified.	2	Each		

 For: **Pakistan International Airlines**

 Seal & Signature
 Of the contractor



27	S/F of Fancy stop/Tee cock 15mm dia high quality as approved by Engineer	12	Each		
28	S/F of upvc Pipe 100 mm dia Sch 40 For Drainage/Sewage complete in all respects, as approved by layout by Engineer incharge.	100	Rft		
29	S/F of upvc Pipe 75 mm For Drainage/Sewage complete in all respects, as approved by layout by Engineer incharge.	100	Rft		
30	Supply and fix CI Spun P-trap, 100 mm dia, all as specified.	6	Each		
31	Stainless steel grating 150mm x 150 mm	4	Each		
32	Coupler Socket 100mm	6	Each		
33	Coupler Socket 75mm	6	Each		
34	S/F of UPVC moulded equal tee/plain/plug 100mm dia	6	Each		
35	S/F of UPVC moulded equal tee/plain/plug 75mm dia	6	Each		
36	S/F of UPVC Elbow 90/45 degree 100mm dia	6	Each		
37	S/F of UPVC Elbow 90/45 degree 75mm dia	6	Each		
38	S/F of Male Female Socket 100 x 75 mm	2	Each		
39	S/F of End Plug 100mm	2	Each		
40	S/F of Cawal 100mm	2	Each		
41	S/F of Y-tee 100mm	4	Each		
42	S/F of Y-tee 75mm	4	Each		
43	SF Of PPR Pipes 20mm for water Supply	100	Rft		
44	S/F of PPR Coupler Socket 20mm	18	Each		
45	S/F of PPR Equal tee 20mm	18	Each		
46	S/F of PPR Reducing Tee (15-20)mm	18	Each		
47	S/F of PPR Elbow 20mm	18	Each		
48	S/F of PPR Socket 20 mm	12	Each		
49	S/F of PPR end cap 20mm	6	Each		
50	S/F of Globe Valve Steel handle including union 20 mm	2	Each		
51	S/F of Globe Valve Steel handle including union 25 mm	2	Each		
52	Supply and fix, Manhole CI cover with frame, 450mm, circular or rectangular exceeding 7.50kg each, but not exceeding 10kg/each, set in CM and hunching in Concrete, as specified.	6	Each		

For: **Pakistan International Airlines**

Seal & Signature
 Of the contractor



ELECTRICAL WORK					
1	P/F of Piano Switch 05 Amp	20	Each		
2	P/F of Piano Socket 05 Amp	14	Each		
3	P/F of wall bracket Fan 30cm	4	Each		
4	P/F of MCCB C/Breaker 06to63A	4	Each		
5	P/F of switch Socket 13Amp (AKAI)	10	Each		
6	P/F of wooden board complete 6x8x2	8	Each		
7	P/F of LED light PHILIPS 12 watts	35	Each		
8	P/F of LED light PHILIPS 18 watts	8	Each		
9	P/F OF WIRE 2.5MM	180	Mtr		
10	P/F light Plug 5amp	38	Each		
11	P/F Extension board	2	Each		
12	P/F Power Plug 15AMP	18	Each		
13	P/F 03 pin breaker 20 amp	6	Each		
14	Building shed lights 18 WATTS	20	Each		
15	Building shed light holders	20	Each		

For: **Pakistan International Airlines**

Seal & Signature
Of the contractor



16	Flood lights 100 watts	3	Each		
17	Exhaust Fan 45 cm	2	Each		
18	Change Over (elec to Genset) 200 Amp breaker	1	Each		
19	LED Ceiling panel lights (2X2)	10	Each		
20	Gate Light fancy complete with holder and lamp of approved type supply and fixing	4	Each		
Total Amount					

SUMMARY

1	CIVIL WORKS	
2	PLUMBING WORKS	
3	ELECTRIC WORKS	
	GRAND TOTAL	

- Must be inclusive of all taxes.
- All contractors are advised to ensure prior visit of site before submitting the tender, for assessment of job, but not mandatory.

For: **Pakistan International Airlines**

Seal & Signature
Of the contractor



ANNEXURE 'A'

PERMIT TO WORK

Seal & Signature
Of the contractor

For: **Pakistan International Airlines**